BANGALORE DIVISION.

Abstract Notification.

The attention of the public is invited to the notification published in pages 26 to 28 of Part VI of the *Mysore Gazette* dated 5th January 1928, calling for the tenders for the work of extending the Vani Vilas Institute at Bangalore.

Last date for the submission of tender 16th January 1928.

Abstract Notification.

The attention of the public is invited to the notice issued in pages 3 and 4 of Part VI of the *Mysore Gazette* dated the 5th January 1928, calling for the tender for the construction of a combined building for the Sub-Registrar's Office and Bonded Depot at Nelamangala.

Last date for the receipt of tenders is 16th January 1928.

R. W. SCALDWELL,
Executive Engineer.

KOLAR DIVISION.

Dated 6th January 1928.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 2 P.M., on 30th January 1928, for constructing an Agricultural Middle School Building at Kagathi, Chintamani Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing an Agricultural Middle School Building at Kagathi" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The quotations should be noted in words as well as in figures.

	Items of work	Per	Rate	Quantity	Cost
			Rs.		Rs.
1	Earthwork	C.yd.		147	
2	Burnt jelly concrete	C.ft.		1033	
3	Burnt stone in mortar	,,		3821	
4	Burnt brick in clay	,,		4777	
4A	Burnt brick in chunam side of doors, etc. ...	,,		400	
5	Burnt stone slabs 6" thick	S.ft.		432	
6	Burnt stone pillars cut and neatly dressed ...	,,		108	
7	Burnt brick in chunam for arch work	C.ft.		152	
8	Plastering with chunam	Sqrs.		86·58	
9	Rough cast work with sand screening and pebbles ...	,,		8·20	
10	Pointing with cement	,,		6·02	
11	Teakwood doors panelled, complete	S.ft.		140	
12	Teakwood windows with glazed shutters inside, complete.	,,		155	
13	Teakwood windows trellis work or expanded metal work.	,,		105	
14	Teakwook wrought and put up with wood oiling ...	C.ft.		234·46	
15	King post truss 10′ span at entrance	No.		1	
16	First class Mangalore tile roofing on teak reepers ...	Sqrs.		43·78	
17	Teakwood eave board ornamental	R.ft.		433	
18	Teakwood final	No.		9	
19	Teakwood planking 1" below valle sheets ...	S.ft.		150	
20	Zinc sheets	,,		180	
21	Ridge tile set in mortar	R.ft.		167	
22	Flooring with Cudapah slab on 3" concrete ...	Sqrs.		22·72	
23	Painting to doors and windows	,,		4·70	
24	Whitewashing	,,		86·58	
25	Ornamental works a round windows, etc. ...	Lump sum			
26	Coping over compound wall	R.ft.		147	
	Total ..	..	..	..	
	Contingencies ...	...	..	..	
	Grand Total ...	..	...	...	

Notice dated 6th January 1928.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division up to 2 P.M., on 1st February 1928, for restoring Seesandra-Thangachikere Minor Tank, R. No. 77—839 of Kolar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the houre of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompained by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 75 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for restoring Seesandra Thangachikere Minor Tank, Kolar Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The quotations should be noted in words as well as in figures.

	Items of work	Per	Rate	Quantity	Cost	Total
	BUND.		Rs. a. p.		Rs.	Rs.
1	Earthwork to bund to R. L. 54·50 with watering and tamping.	C.yd.		882		
2	New [illegible]one revetment	"		272		
3	Turfin[illegible]	S.yd.		1536		
4	Chisel[illegible], painting and fixing grade stone	No.		11		
5	Provi[illegible]g a new Reg. No. stone ...	"		1		
6	[illegible] new gauge stone ...	"		1		
7	[illegible] date stone	"		1		
8	Clearing [illegible]ungle thick	L. S.				
9	Refixing [illegible]d index stones	No.		11		
10	Cutting [illegible]enches and picking top of bund.	Grade		11		
11	Forming the flank bund	L. S.				
	Total ...	...		...		
	WASTE WEIR 60' LONG.					
1	Earthwork excavating foundation ...	C.yd.		70		
2	Surki concrete	C.ft.		121		
3	Burnt brick in surki mortar ...	"		345		
4	Surki plastering	Sqr.		5·10		
5	Burnt stone slabs dressed	S.ft.		228		
6	New stone work	C.yd.		51		
7	Clearing draft and approach ...	L. S.				
8	Cutting joggles	No.		10		
	Total ...	...		...		
	SLUICES.					
1	Repairing old sluice and providing front and rear cisterns.	L. S.				
	MISCELLANEOUS.					
	Compensation for lands	...		...		
	Grand Total ...	...		...		

N. G. KRISHNA IYENGAR,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification.

The attention of the public is invited to the notice, calling for tenders for constructing Sub-Registrar's Office and Bonded Warehouse at Kunigal, published in the *Mysore Gazette* dated 5th January 1928, Part VI, pages 6 and 7. The last date of presenting the tender is 28th January 1928.

V. V. PATANKAR,
Executive Engineer.